Purchasing Division
Finance Department

Room 120
411 West First Street
Duluth, Minnesota 55802

218-730-5340
purchasing@duluthmn.gov

Addendum 2
Solicitation 24-99400
Raleigh Street Reconstruction

This addendum serves to notify all bidders of the following changes to the solicitation documents:

DRAWINGS
There are no revisions to the drawings under this addendum.

SPECIFICATIONS
Add to the Specifications:
SP 68 (2504.602) Connect to Existing Watermain

At Sta 100+60 the Contractor shall provide the necessary excavation for the connection to the existing watermain. The excavation shall completely encircle the existing steel main, providing minimum clearance for installation of 30" in all directions, and trench in the direction of the branch main of sufficient length to accommodate the main tapping equipment. In that excavation the City of Duluth will install a weld-on side saddle branch main fitting with a 12" gate valve, these materials will be provided by the City. The City will test the branch saddle assembly and tap the existing live water main for the Contractor. The City will install cathodic coatings on the new connection fitting and anodes on the new valve. The Contractor will then connect to the new 12" HDPE water main to the new 12" valves MJ end, and be responsible for the pipe embedment, backfilling, and the new valve box assembly. The schedule of this work shall be coordinated with the City Project Engineer with a minimum 10 days' notice.

Please acknowledge receipt of this Addendum by checking the acknowledgement box within the www.bidexpress.com solicitation.

Posted: **April 17, 2024**