**Purchasing Division**
*Finance Department*

Room 120
411 West First Street
Duluth, Minnesota 55802

218-730-5340
purchasing@duluthmn.gov

**Addendum # 3**
**Solicitation # 23-99774**
**Lead Water Service Replacement – Gary Neighborhood**

## NOTICE

This Addendum is issued to modify, explain or correct the original drawings, specifications and/or previous addenda and is hereby made a part of the Contract Documents.

## CHANGES TO DRAWINGS

1. Pay Item 2451.607 Granular Bedding is hereby added to the SEQ and bid form as follows:

| NOTES | LINE NUMBER | SPEC NUMBER | DESCRIPTION | UNIT | TOTAL EST-QUANTITY |
|---|---|---|---|---|---|
| | 17A | 2451.607 | GRANULAR BEDDING | CU YD | 100 |

## CHANGES TO SPECIAL PROVISIONS

1. Delete **SP 32.2** in its entirety and replace with the following:
    a. METHOD OF MEASUREMENT
        i. Granular bedding shall be measured as the compacted volume as placed in the field and paid under item 2451.607 GRANULAR BEDDING at the contract bid price per cubic yard and shall include all costs for placing and compacting bedding material and removal and disposal of displaced material.

## RESPONSES TO BIDDER QUESTIONS

1. **Question:** Please clarify what is "light" cleaning vs. "Heavy" Cleaning: Specifically, is jetting considered 'light" or "heavy" work?
    a. **Response:** Light cleaning shall be defined as flushing (multiple passes, as needed) by utilizing hose(s), nozzle(s), and available water pressures at the site and light mechanical effort to remove accumulated sediment or debris from the pipe to access the pipe and/or complete the work. Heavy cleaning (root cutting, removal of heavy deposits, or high-pressure jetting), if required, will be paid for

as extra work.

**SUPPLEMENTAL INFORMATION**

None.

Please acknowledge receipt of this Addendum by checking the acknowledgement box within the www.bidexpress.com solicitation.

Posted: **January 4, 2024**

**END OF ADDENDUM**