Purchasing Division
Finance Department

Room 120
411 West First Street
Duluth, Minnesota 55802

218-730-5340
purchasing@duluthmn.gov

Addendum 5
Solicitation 24-99200
Lower Spirit Nordic Trail Construction

This addendum serves to notify all bidders of the following changes to the solicitation documents:

Questions: The following questions have been asked and are answered in *italics*

1. Not sure why the 2.0k loop has 2,080.00 lin. ft. of subgrade excavation and the small loop on the bid form doesn't have that line item. Sub grade excavation is usually bed preparation. So I'm not quite sure if it's trail preparation?
    a. *SP-20 (2105) EXCAVATION AND EMBANKMENT: **ADD** The bid item Subgrade Preparation to be used for the 2.0 km Connector shall consist of removing rocks, debris, and stumps from the trail area and filling holes as needed utilizing surrounding borrow material in order to create a passable ski trail surface that meets the typical section specified in the plans for the 2.0 km connector.*

Please acknowledge receipt of this Addendum by checking the acknowledgement box within the www.bidexpress.com solicitation.

Posted: **February 13, 2024**